



**INTERCONNECTION  
FACILITIES STUDY  
REPORT**

GEN-2019-019

Published February 2025

By SPP Generator Interconnections Dept.

## REVISION HISTORY

---

<b>DATE OR VERSION NUMBER</b>	<b>AUTHOR</b>	<b>CHANGE DESCRIPTION</b>
February 5, 2025	SPP	Initial draft report issued.
February 18, 2025	SPP	TO-proposed revisions made. Final report issued.

# CONTENTS

---

Revision History .....	i
Summary .....	1
Introduction .....	1
Phase(s) of Interconnection Service .....	1
Compensation for Amounts Advanced for Network Upgrade(s).....	1
Interconnection Customer Interconnection Facilities .....	2
Transmission Owner Interconnection Facilities and Non-Shared Network Upgrade(s) .....	3
Shared Network Upgrade(s) .....	4
Contingent Network Upgrade(s).....	5
Affected System Upgrade(s) .....	6
Conclusion.....	7
Appendices .....	8
A: Transmission Owner’s Interconnection Facilities Study Report and Network Upgrades Report(s).....	9

## SUMMARY

---

### INTRODUCTION

This Interconnection Facilities Study (IFS) for Interconnection Request GEN-2019-019 is for a 15.15 MW generating facility located in Sioux County, IA. The Interconnection Request was studied in the DISIS-2018-002/DISIS-2019-001 Impact Study for ER/NR. The Interconnection Customer's requested in-service date is January 30, 2027.

The interconnecting Transmission Owner, Northwest Iowa Power Cooperative (NIPCO), performed a detailed IFS at the request of SPP. The full report is included in Appendix A. SPP has determined that full Interconnection Service will be available after the assigned Transmission Owner Interconnection Facilities (TOIF), Non-Shared Network Upgrades, Shared Network Upgrades, Contingent Network Upgrades, and Affected System Upgrades that are required for full interconnection service are completed.

The primary objective of the IFS is to identify necessary Transmission Owner Interconnection Facilities, Network Upgrades, other direct assigned upgrades, cost estimates, and associated upgrade lead times needed to grant the requested Interconnection Service.

### PHASE(S) OF INTERCONNECTION SERVICE

It is not expected that Interconnection Service will occur in phases. However, full Interconnection Service will not be available until all Interconnection Facilities and Network Upgrade(s) can be placed in service.

### COMPENSATION FOR AMOUNTS ADVANCED FOR NETWORK UPGRADE(S)

FERC Order ER20-1687-000 eliminated the use of Attachment Z2 revenue crediting as an option for compensation. The Incremental Long Term Congestion Right (ILTCR) process will be the sole process to compensate upgrade sponsors as of July 1st, 2020.

## **INTERCONNECTION CUSTOMER INTERCONNECTION FACILITIES**

The Generating Facility is proposed to consist of one (1) 14.5 MW gas turbine and one (1) 1.71 MW steam turbine for a total generating nameplate capacity of 15.15 MW.

The Interconnection Customer's Interconnection Facilities to be designed, procured, constructed, installed, maintained, and owned by the Interconnection Customer at its sole expense include:

- 12.47 kV underground cable collection circuits;
- All 12.47 Distribution facilities required to connect the Interconnection Customer's Generator Facilities to the POI;
- Generation and 12.47 kV Distribution equipment at the Interconnection Customer's Generator Facility necessary to maintain a composite power delivery at continuous rated power output at the high-side of the generator substation at a power factor within the range of 95% lagging and 95% leading in accordance with Federal Energy Regulatory Commission (FERC) Order 827. The Interconnection Customer may use inverter manufacturing options for providing reactive power under no/reduced generation conditions. The Interconnection Customer will be required to provide documentation and design specifications demonstrating how the requirements are met; and,
- All necessary relay, protection, control and communication systems required to protect Interconnection Customer's Interconnection Facilities and Generating Facilities and coordinate with Transmission Owner's relay, protection, control and communication systems.

**TRANSMISSION OWNER INTERCONNECTION FACILITIES AND NON-SHARED NETWORK UPGRADE(S)**

To facilitate interconnection, the interconnecting Transmission Owner will perform work as shown below necessary for the acceptance of the Interconnection Customer’s Interconnection Facilities.

**Table 1** and **Table 2** list the Interconnection Customer’s estimated cost responsibility for Transmission Owner Interconnection Facilities (TOIF) and Non-Shared Network Upgrade(s) and provides an estimated lead time for completion of construction. The estimated lead time begins when the Generator Interconnection Agreement has been fully executed.

*Table 1: Transmission Owner Interconnection Facilities (TOIF)*

<b>Transmission Owner Interconnection Facilities (TOIF)</b>	<b>Total Cost Estimate (\$)</b>	<b>Allocated Percent (%)</b>	<b>Allocated Cost Estimate (\$)</b>
<u>Transmission Owner's Siouxland 69kV GEN-2019-019 Interconnection (TOIF) (NIPCO) (UID 143689): Facilitate the interconnection of GEN-2019-019 Estimated Lead Time: 12 Months</u>	\$1,176,290	100.00%	\$1,176,290
<b>Total</b>	<b>\$1,176,290</b>		<b>\$1,176,290</b>

*Table 2: Non-Shared Network Upgrade(s)*

<b>Non-Shared Network Upgrades Description</b>	<b>ILTCR</b>	<b>Total Cost Estimate (\$)</b>	<b>Allocated Percent (%)</b>	<b>Allocated Cost Estimate (\$)</b>
<u>Transmission Owner's Siouxland 69kV GEN-2019-019 Interconnection (Non-shared NU) (NIPCO) (UID 143690): Facilitate the interconnection of GEN-2019-019 Estimated Lead Time: 12 Months</u>	Ineligible	\$1,167,956	100%	\$1,167,956
<b>Total</b>		<b>\$1,167,956</b>		<b>\$1,167,956</b>

**SHARED NETWORK UPGRADE(S)**

The Interconnection Customer’s share of costs for Shared Network Upgrades is estimated in **Table 3** below.

*Table 3: Interconnection Customer Shared Network Upgrade(s)*

Shared Network Upgrades Description	ILTCR	Total Cost Estimate (\$)	Allocated Percent (%)	Allocated Cost Estimate (\$)
<u>NA</u>				
<b>Total</b>		<b>\$0</b>		<b>\$0</b>

All studies have been conducted assuming that higher-queued Interconnection Request(s) and the associated Network Upgrade(s) will be placed into service. If higher-queued Interconnection Request(s) withdraw from the queue, suspend or terminate service, the Interconnection Customer’s share of costs may be revised. Restudies, conducted at the customer’s expense, will determine the Interconnection Customer’s revised allocation of Shared Network Upgrades.

**CONTINGENT NETWORK UPGRADE(S)**

Certain Contingent Network Upgrades are **currently not the cost responsibility** of the Interconnection Customer but will be required for full Interconnection Service.

*Table 4: Interconnection Customer Contingent Network Upgrade(s)*

<b>Contingent Network Upgrade(s) Description</b>	<b>Current Cost Assignment</b>	<b>Estimated In-Service Date</b>
NA		

Depending upon the status of higher- or equally-queued customers, the Interconnection Request’s in-service date is at risk of being delayed or Interconnection Service is at risk of being reduced until the in-service date of these Contingent Network Upgrades.



**AFFECTED SYSTEM UPGRADE(S)**

To facilitate interconnection, the Affected System Transmission Owner will be required to perform the facilities study work as shown below necessary for the acceptance of the Interconnection Customer’s Interconnection Facilities. **Table 5** displays the current impact study costs provided by either MISO or AECI as part of the Affected System Impact review. The Affected System facilities study could provide revised costs and will provide each Interconnection Customer’s allocation responsibilities for the upgrades.

*Table 5: Interconnection Customer Affected System Upgrade(s)*

<b>Affected System Upgrades Description</b>	<b>Total Cost Estimate (\$)</b>	<b>Allocated Percent (%)</b>	<b>Allocated Cost Estimate (\$)</b>
NA			
<b>Total</b>	<b>\$0</b>		<b>\$0</b>

## CONCLUSION

After all Interconnection Facilities and Network Upgrades have been placed into service, Interconnection Service for 15.15 MW can be granted. Full Interconnection Service will be delayed until the TOIF, Non-Shared NU, Shared NU, Contingent NU, Affected System Upgrades that are required for full interconnection service are completed. The Interconnection Customer's estimated cost responsibility for full interconnection service is summarized in the table below.

*Table 6: Cost Summary*

<b>Description</b>	<b>Allocated Cost Estimate</b>
Transmission Owner Interconnection Facilities Upgrade(s)	\$1,176,290
Non-Shared Network Upgrade(s)	\$1,167,956
Shared Network Upgrade(s)	\$0
Affected System Upgrade(s)	\$0
<b>Total</b>	<b>\$2,344,246</b>

Use the following link for Quarterly Updates on upgrades from this report: <https://spp.org/spp-documents-filings/?id=18641>

A draft Generator Interconnection Agreement will be provided to the Interconnection Customer consistent with the final results of this IFS report. The Transmission Owner and Interconnection Customer will have 60 days to negotiate the terms of the GIA consistent with the SPP Open Access Transmission Tariff (OATT).

# APPENDICES

---

**A: TRANSMISSION OWNER'S INTERCONNECTION FACILITIES STUDY  
REPORT AND NETWORK UPGRADES REPORT(S)**

See next page for the Transmission Owner's Interconnection Facilities Study Report and Network Upgrades Report(s).

# Northwest Iowa Power Cooperative Interconnection Facilities Study GEN-2019-019

## 1. Background:

- 1.1 Per SPP Generation Interconnection Process 2019 revision<sup>1</sup>, Northwest Iowa Power Cooperative (NIPCO) received a request to perform an Interconnection Facility Study Analysis for the following Interconnection Requests:

GI Request #	Point of Interconnection	Capacity (MW)	Fuel Type	Comments
GEN-2019-019	J15 Switching Station 69 kV	15.15	Thermal	Please provide interconnection upgrades and costs estimates needed to interconnection into the POI (SCERT UIDs# 143690 and 143689).

<sup>1</sup> SPP Tariff Attachment V Generator Interconnection Procedures (GIP) Section 8.4.4

## 2. Study Requirements:

NIPCO has performed this Interconnection Facility Study Analysis in accordance with SPP Tariff Attachment V, Generator Interconnection Procedures (GIP) Section 8.4.4 for the Interconnection Request(s) as described in Section 1.

2.1. The Interconnection Facility Study Analysis includes an evaluation of the following:

- 2.1.1. Perform/develop a substation layout, perform a preliminary bus design, determine all electrical equipment requirements, and if required determine a suitable site location to accommodate the Request. Develop/compile cost estimates for all NIPCO labor, overheads, equipment additions, modifications, etc. to accommodate the generator interconnection.
- 2.1.2. Develop an overall construction schedule for completion of the necessary additions and/or modifications.
- 2.1.3. Point Of Change of Ownership. For the purposes of this Study Analysis, the Point of Change of Ownership location is defined as the line side of the visual open switch just outside NIPCO's Garfield Substation where the Interconnection Customer's underground 12.47 kV line(s) connects to the visual open switch. Interconnection Customer will furnish and install the underground conductor and terminator assembly to the visual open switch.
- 2.1.4. Other Interconnection/Metering Requirements. Basic indication, metering, monitoring, control, and relaying requirements due to a generator interconnection are included in the cost estimate. NIPCO's generation metering requirements, as an SPP Transmission Owner, must be met.

### **3. Study Results for GEN-2019-019:**

**3.1.** The following results document the analysis of the required facilities for this Interconnection Request as outlined in Section 1 for a new 69kV line terminal at the J15 69kV Switching Station, new 69 kV tap line, and new 12.47/69 kV generator step up substation (Garfield). NIPCO has determined that the following additions and improvements are required to maintain a safe and reliable interconnection to NIPCO's transmission system.

#### **3.2 Switching Station**

A 69kV terminal addition was built to accommodate the new generation resource interconnection. This terminal was added to the existing straight bus switching station. Reference Figure A1. All equipment followed NIPCO's internal design standards for minimum BIL, ampacity, and fault capabilities.

The associated work for the new 69kV line terminal included the following major additions:

- (1) 69kV Relaying Panel
- (1) 69kV Breaker
- (6) 69kV Breaker Disconnect Switches
- (1) Set of Line Surge Arrestors

Additional associated work included a review and update to relay/protection schemes and SCADA RTU configurations at the J15 Switching Station.

#### **3.3 Tap Line**

A 69kV tap line was built to accommodate the new generation resource interconnection. This tap line consists of 0.75 miles of 4/0 ACSR single circuit and 2 miles of 477 ACSR double circuit with an existing 69kV transmission line connecting to the J15 69kV Switching Station. Reference Figure A2. All equipment followed NIPCO's internal design standards for minimum BIL, ampacity, and fault capabilities.

#### **3.4 Generator Step Up Substation**

A 12.47/69kV, 12/16/20 MVA generator step up substation was built to accommodate the new generation resource interconnection. This substation connects to the 12.47kV underground cable from the Interconnection Customer and to the tap line to the J15 69kV Switching Station. Reference Figure A3. All equipment followed NIPCO's internal design standards for minimum BIL, ampacity, and fault capabilities.

The associated work for the new 12.47/69kV generator step-up substation included:

- (1) Land lease, grading, rock, ground grid, fencing
- (1) Control Building
- (1) Communications Rack
- (1) Battery Rack
- (1) Relaying Rack
- (1) 69kV Line Take-Off Structure
- (1) Set of Line Surge Arrestors
- (1) Set of Line PTs
- (6) 69kV Breaker Disconnect Switches
- (1) 69kV Breaker
- (1) 12.47/69kV, 12/16/20 MVA transformer
- (1) Set of 12.47kV Single-Phase Voltage Regulators
- (1) 12.47kV Underground Riser Structure
- (1) 12.47kV Visual Open Switch

### **3.5 Environmental Requirements**

Compliance with all applicable federal, state and local regulations were strictly adhered to. Additionally, all applicable and required permits and approvals were obtained prior to construction.

### 3.6 Cost Estimate

<b>GEN-2019-019 Estimated Costs Non Shared Network Upgrades</b>	<b>Current Year \$</b>
<b>Line Costs</b>	
Engineering Labor	\$41,401
Construction Labor	\$523,783
Reactive Compensation (Labor & Materials)	\$0
Material	\$423,950
Right of Way	\$4,600
<b>Line Sub Total</b>	<b>\$993,734</b>
<b>Station Costs</b>	
Engineering Labor	\$62,102
Construction Labor	\$61,666
Site Property Rights	\$0
Reactive Compensation	\$0
Material	\$50,454
Right of Way	\$0
<b>Station Sub Total</b>	<b>\$174,221</b>
AFUDC	\$0
Contingency	\$0
<b>Non - Shared Network Upgrades total</b>	<b>\$1,167,956</b>


<b>GEN-2019-019 Transmission Owner Interconnect Facilities</b>	<b>Current Year \$</b>
<b>Line Costs</b>	
Engineering Labor	\$40,935
Construction Labor	\$295,337
Reactive Compensation (Labor & Materials)	\$0
Material	\$241,639
Right of Way	\$0
<b>Line Sub Total</b>	<b>\$577,911</b>
<b>Station Costs</b>	
Engineering Labor	\$61,403
Construction Labor	\$295,337
Site Property Rights	\$0
Reactive Compensation	\$0
Material	\$241,639
Right of Way	\$0
<b>Station Sub Total</b>	<b>\$598,379</b>
AFUDC	\$0
Contingency	\$0
<b>TOIF Subtotal</b>	<b>\$1,176,290</b>

<b>TOTAL INTERCONNECTION COST</b>	<b>\$2,344,246</b>
-----------------------------------	--------------------



# Figure A1: J15 Switching Station One-Line Diagram

Plot Date: 7/26/2021 9:26:40 AM



### GENERAL LEGEND

- 69 kV bus
  - 69 kV bypass
  - 7.2 kV circuit
  - PT, CT circuit
  - Potential transformer
  - Station Service XFMR
  - Current Transformer
  - Vee Center Break GOAB Switch
  - Hook stick Disconnect Switch
  - Fused Disconnect
  - Lightning Arrester
- (\*) Number of devices (if more than one)

### MAJOR EQUIPMENT

- (1) Surge Arrester, 60 kV Class, 48 kV PVI MCOV
- (2) Hook stick Disconnect Switch, 69 kV, rating as shown
- (3) Mitsubishi circuit breaker, SF6, 72.5 kV, 2000 A, 40KA
- (4) Vee Center break GOAB Switch, 69 kV, 600 A
- (5) PT, 69 kV Primary, 115/67 V Sec, 350/600:1 PTR
- (6) Soloman Xfmr, 69 kV Primary, 120/240 V Sec, 100 kVA
- (7) CT, 2000:5 OBCT, C400, RF=2.0

P:\04\225\00\DWG\J15\J15-100.DWG

REV	DATE	DESCRIPTION
0	8-6-14	ISSUED FOR CONSTRUCTION
1	3-20-2015	CONFORMING TO CONSTRUCTION RECORDS
1B	08-09-2021	ISSUED FOR CONTROL PANEL P6 FARIICATION - BREAKER 1518 ADDITION



Project Manager: TWM  
 Designer: AMR  
 Project Number: 422506  
 Phone: (712) 472-2531



NORTHWEST IOWA POWER COOPERATIVE  
 P. O. Box 240, 31002 C38  
 Le Mars, IOWA 51031-0240

SWITCHING ONE-LINE  
 J15 SWITCHING STATION

S  
H  
E  
E  
T  
 J15-100



# Figure A3: Garfield Step-Up Substation One-Line

P&ID Date: 9/29/2021 9:57:19 AM

P:04/25/25/00/DWG/GE-100.DWG

### GENERAL LEGEND


- 69 kV circuit
- 12.47 kV circuit
- - - - 12.47 kV underground circuit
- ⊕ Wye, grounded
- Δ Delta
- ← - - - Underground transition



NORTH

### MAJOR EQUIPMENT

BAV	DEVICE	DESCRIPTION	MFR	CATALOG NUMBER	QTY
①	602-1	69 kV L.A.	HUBBELL	300048-3001	3
②	602-2	69 kV PT	GE	JVS-350	3
③	612LS	69 kV HOOKSTICK	ROYAL	13015TSTD	3
④	612	69 kV BREAKER	MEPPI	PO 5747	1
⑤	604-1	67/12.47 kV XFMR	VIRGINIA	D312A, 47012MA216	1
		L.A. - HIGH	HUBBELL	EV9004800-3001	3
		L.A. - LOW	HUBBELL	EV9009900-3001	3
⑥	701-1	COMBINATION P/CT	ARTECHE	770084151	3
⑦	703-1	REGULATORS			
⑧	1-3	VOLTAGE REGULATORS, 500 kVA, 656 A, 7.62 kV +/- 10%, 32 STEP, 95 kV BIL	SIEMENS	SERIAL #5362470-2, 3, 4	3
⑨	4-6	REGULATOR BYPASS, 15 kV, 110 kV BIL, 1200 A, CYPOXY	S&C	333602-E	3
⑩	LA	CONTROLLER, SEL-2431 WITH SIEMENS RETROFIT HARNESS	SEL	24310011X11221XXX10XX KEY 3924	3
⑪	LA	LIGHTNING ARRESTER, 8.4 kV MCOV, DISTRIBUTION CLASS	EATON	UHS10059A1A1B1A	3
⑫	800-1	DISCONNECT SWITCH, 15 kV, 1200 AMP, HOOKSTICK	ROYAL	BT 13005	3
⑬	700-2	VOS	SPS	QUOTE 321-72	1
⑭	700-1	12.47 kV L.A.	HUBBELL	EV9009900-3001	3
		LIGHTNING ARRESTER, 8.4 kV MCOV, STATION CLASS	HUBBELL	EV9009900-3001	3



### DESIGN NOTES

- ⚠ Garfield substation may be referred to as the GSU substation on other plans.
- ⚠ Verify revenue meter locations.
- ⚠ Verify 52a/52b interlock of 52S, 52G, and 52F1.
- ⚠ Verify connection of steam let down generator.
- ⚠ Grounding transformer? Check PPS drawings.

- ⚠ Distribution connections to be determined.
- ⚠ Visual open switch terminal connections: NIPCO Side = 2 bushings per Ø. Customer side = 3 bushings per Ø. All 1200 A bushings.

### REVISION NOTES

- ⚠ See Design notes F, G, and clouds.
- ⚠ Rotated switchgear to reflect physical layout at CHP facility. Showing distribution switches and circuitry. See clouds.


### NOTES (CONTRACTOR)

- ⚠ Major equipment furnished by NIPCO and installed by this Contractor.
- ⚠ GSU transformer is on site. To be moved into place by others and coordinated by NIPCO.
- ⚠ See demarcation line. All SEC equipment is out of this substation contractor's scope and will be furnished and installed by others. The SEC equipment is shown for reference purposes only.
- ⚠ Substation steel delivered to site by others and received, unloaded, and installed by this Contractor.
- ⚠ Communication building delivered and set by NIPCO.
- ⚠ Contractor shall be responsible for transporting all other equipment from the Owner's storage facility located in LeMars, IA to the project location. This equipment includes but is not limited to: breaker, switches, instrument transformers, voltage regulators, and control equipment.
- ⚠ Contractor shall furnish and install materials as indicated on the material list. See sheet GF-350 for details.
- ⚠ Contractor to install Owner-furnished visual open padmount switch and associated fiberglass box pad. 15 kV power cable between 700-1 and SW1 shall be furnished, installed, and terminated by this Contractor.

### NOTES (DISTRIBUTION)

- ⚠ Normally open from Siouxland #2 @ switch #3; Bay locked open + 600A elbows parked. NW REC to internally document operating/locking procedure.

### \*\*FOR CONCEPTUAL PURPOSES ONLY - SEE 19026-EOL-601 FOR DETAILS\*\*



BY THIS CONTRACTOR ← → BY OTHERS

REV	DATE	DESCRIPTION
G	10-01-2021	ISSUED FOR CONSTRUCTION WIRING



Project Manager: TWMM  
 Designer: AMR  
 Project Number: 422526  
 Phone: (712) 472-2531



**SWITCHING ONE-LINE  
GARFIELD SUBSTATION**

S  
H  
E  
E  
T  
GF-100